

Contracts Management

Date: August 5, 2013
To: Potential Offerors
From: Gary L. Callahan, Senior Contracts Manager
Re: **Solicitation Addendum # 6 to RFP 13-0637 / East Hawaii Region
Design-Build Turnkey Angiography Suite**

This correspondence serves as Addendum # 6 to the subject Request for Proposals (“RFP”). Your response to this RFP should be governed by the content of the original RFP and the revisions / corrections / additions / clarifications provided in this addendum notice.

Please note that the “Submission Deadline for Questions & Clarification Requests” remains:

3:00 PM, HST, Thursday, August 15, 2013

The Request for Proposals shall be amended to include the following change:

1. The following line item project is hereby added to the **SCOPE OF WORK, Section 2.0** which begins on page 6:

“Additional Scope of Work Line Item:

The areas labeled “IB-65” and “IB-62” are slated to be repurposed for the Ultrasound Department. The proposed Ultrasound suite will necessitate demolition and reconstruction prior to the demolition phase of the current Ultrasound suite (Area IB-83) as referenced in RFP #13-0637.

IB-62 demolition:

1. Remove all counters, including sink.
2. Remove lead lined control booth wall.
3. Remove lavatory door.
4. Remove lead lined IB-62 wall and door (note ceiling height discrepancy between IB-62 and IB-65).
5. Remove floor tile.

IB-62 construction:

1. Install sinks, counters, and cabinets.
2. Install curtain tracks.
3. Install vinyl flooring and baseboards.
4. Reconfigure electrical: data/phone, power, and lighting.
5. Install can lights.
6. Reconfigure ceiling grid and install new ceiling tile.
7. Sheet rock raceway located in the walls.

8. Sheet rock lavatory door.
9. Patch all walls.
10. Paint.

IB-65 construction:

1. Reconfigure electrical: data/phone, power, and lighting.
2. Install can lights.
3. Reconfigure curtain tracks.

Sheet rock and paint IB-60 entry way (disassemble automatic door/keypad).